NO. PERSONS / 3RD FLOOR = 187 (WAS CALCULATED FROM CLASSROOMS AND LABORATORIES)
NR. PERSOANE / ETAJ 3 = 187 (S-A CALCULAT SI PENTRU LABORATOARE)



LEGEND/LEGENDA:

NEW WORKS/LUCRARI NOI

EIII 12
DENTAL SOURGEON CABINET
STOMATOLOGIC

EIII 10
I.T. LABORATORY
LABORATOR I.T.

EIII 09
FOREIGN LANGUAGE CABINET
CABINET LIMBI STRAINE

EIII 11
STAIRCASE
CASA SCARII

EIII 07
BOYSRESTROOM
G.S. SAIETI

EIII 08
GIRLS RESTROOM
G.S. FETE

EIII 06
STAIRCASE
CASA SCARII

EIII 01
CORRIDOR / CORIDOR

EIII 02
CLASSROOM
SALA CLASA

EIII 03
CLASSROOM
SALA CLASA

EIII 04
CLASSROOM
SALA CLASA

EIII 05
CLASSROOM
SALA CLASA

THERMAL INSULATION OF EXTRUDED POLYSYRENE 3CM
TERMOIZOLATIE POLISTIREN EXPANDAT 3CM

THERMAL INSULATION OF EXPANDED POLYSYRENE 5CM
TERMOIZOLATIE POLISTIREN EXPANDAT 5CM

ACC WALL 15 CM; FIRE RATED 150 MIN
ZIDARIE BCA 15CM REZISTENTA LA FOC 150MIN

FIRE RATED DOOR 15 MIN WITH AUTOMATIC DOOR CLOSER
USA REZISTENTA LA FOC 15 MIN, CU SISTEM DE AUTONCHIDERE

TABLOU ELECTRIC

AREA AND FINISHING TABLE
TABEL SUPRAFETE SI FINISAJE

NO. NR	ROOM NAME FUNCTIUNEA	UTILE AREA(SQM) SUPRAFATA UTILA (MP)	FLOOR PARDOSEALA	WALLS PERETI	CEILING TAVANE
EIII 01	CORRIDOR CORIDOR	97.9	CAST TERRAZZO MOZAIC TURNAT	WASHABLE PAINT VOPSITORIE LAVABILA DE INTERIOR	WASHABLE PAINT VOPSITORIE LAVABILA DE INTERIOR
EIII 02	CLASSROOM SALA CLASA	49.9	PVC FLOORING COVOR PVC	WASHABLE PAINT VOPSITORIE LAVABILA DE INTERIOR	WASHABLE PAINT VOPSITORIE LAVABILA DE INTERIOR
EIII 03	CLASSROOM SALA CLASA	50.4	PVC FLOORING COVOR PVC	WASHABLE PAINT VOPSITORIE LAVABILA DE INTERIOR	WASHABLE PAINT VOPSITORIE LAVABILA DE INTERIOR
EIII 04	CLASSROOM SALA CLASA	50.4	PVC FLOORING COVOR PVC	WASHABLE PAINT VOPSITORIE LAVABILA DE INTERIOR	WASHABLE PAINT VOPSITORIE LAVABILA DE INTERIOR
EIII 05	CLASSROOM SALA CLASA	50.0	PVC FLOORING COVOR PVC	WASHABLE PAINT VOPSITORIE LAVABILA DE INTERIOR	WASHABLE PAINT VOPSITORIE LAVABILA DE INTERIOR
EIII 06	STAIRCASE CASA SCARII	17.9	CAST TERRAZZO MOZAIC TURNAT	WASHABLE PAINT VOPSITORIE LAVABILA DE INTERIOR	WASHABLE PAINT VOPSITORIE LAVABILA DE INTERIOR
EIII 07	BOYS G.S. BAIETI	19.1	STONEWARE TILES PLACAJE CERAMICE	CERAMIC TILES, H=2.10M, WASHABLE PAINT PLACAJE CERAMICE PANA LA +2.10M, VOPSITORIE LAVABILA DE INTERIOR	WASHABLE PAINT VOPSITORIE LAVABILA DE INTERIOR
EIII 08	GIRLS G.S. FETE	27.9	STONEWARE TILES PLACAJE CERAMICE	CERAMIC TILES, H=2.10M, WASHABLE PAINT PLACAJE CERAMICE PANA LA +2.10M, VOPSITORIE LAVABILA DE INTERIOR	WASHABLE PAINT VOPSITORIE LAVABILA DE INTERIOR
EIII 09	FOREIGN LANGUAGE CABINET CABINET LIMBI STRAINE	50.4	PVC FLOORING COVOR PVC	WASHABLE PAINT VOPSITORIE LAVABILA DE INTERIOR	WASHABLE PAINT VOPSITORIE LAVABILA DE INTERIOR
EIII 10	I.T. LABORATORY LABORATOR I.T.	50.5	PVC FLOORING COVOR PVC	WASHABLE PAINT VOPSITORIE LAVABILA DE INTERIOR	WASHABLE PAINT VOPSITORIE LAVABILA DE INTERIOR
EIII 11	STAIRECASE CASA SCARII	17.1	CAST TERRAZZO MOZAIC TURNAT	WASHABLE PAINT VOPSITORIE LAVABILA DE INTERIOR	WASHABLE PAINT VOPSITORIE LAVABILA DE INTERIOR
EIII 12	DENTAL SURGEON CAB. CAB. STOMATOLOGIC	15.5	STONEWARE TILES PLACAJE CERAMICE	CERAMIC TILES, H=2.10M, WASHABLE PAINT PLACAJE CERAMICE PANA LA +2.10M, VOPSITORIE LAVABILA DE INTERIOR	WASHABLE PAINT VOPSITORIE LAVABILA DE INTERIOR
		UTILE AREA/SUPRAFATA UTILA SU= 496.6 MP			
		BUILD-UP AREA/SUPRAFATA CONSTRUITA SC= 557.5 MP			

NOTE: - ALL STONEWARE FLOORINGS SHALL BE HEAVY TRAFFIC, SKID PROOF.
- IN THE CHEMISTRY AND BILOLOGY LABORATORIES, INCLUDING THE ANEXES, THE STONEWARE FLOORINGS SHALL BE HEAVY TRAFFIC, SKID PROOF AND ACID RESISTANT.
- ALL PARQUET AND PVC FLOORINGS SHALL BE HEAVY TRAFFIC.
NOTA: - SE VA FOLOSI NUMAI GRESIE DE TAFIC INTENS SI ANTIDERAPANTA
- IN LABORATOARELE DE CHIMIE SI BIOLOGIE, INCLUSIV ANEXELE, GRESIA VA FI DE TRAFIC INTENS, ANTIDERAPANTA SI REZISTENTA CHIMIC.
- PARDOSELILE DIN PARCHET SI COVOR PVC VOR FI DE TRAFIC INTENS.

NOTA: ALL MEASUREMENTS SHOULD BE MADE ON SITE/TOATE MASURATORILE SA SE FACA LA FATA LOCULUI

VERIFICATOR M.L.P.A.T.	NAME/NUME	SIGN./SEMNATURA	DEMANDICER/INTA	REFERAT / EXPERTIZA NR. / DATA

PROJECT COORDINATOR/COORDINATOR PROIECT: THE LOUIS BERGER GROUP, INC

BUCHAREST SCHOOL INFRASTUCTURE REHABILITATION / REABILITAREA INFRASTRUCTURII EDUCATIONALE IN MUNICIPIUL BUCURESTI

DESIGNER/PROIECTANT: CONSILIER CONSTRUCT

	M4				
	M3				
	M2				
	M1				
	Modif	Date/Data	PROJECTED/PROIECTAT	VERIFIED/VERIFICAT	PROJ. DIR./SEF PROIECT

BENEFICIARY/BENEFICIAR: **MUNICIPALITY OF BUCHAREST / PRIMARIA MUNICIPIULUI BUCURESTI**

SCHOOL NAME/ NUME SCOALA: **ELEMENTARY SCHOOL No. 310/SCOALA GENERALA Nr. 310**

	NUME	SEMNATURA
DESIGNED BY PROIECTAT	ARH. R. LAZAR	
VERIFIED BY VERIFICAT	ARH. O. HORIARESCU	
PROJ.DIR. SEF PROIECT	ARH. S. ICHIM	

TYPE OF WORKS/ LUCRARE: **ARHITECTURAL WORKS/LUCRARE DE ARHITECTURA**
BUILDING A-SCHOOL, CORP A-SCOALA

DRAWING/ PLANSA: **3 RD FLOOR PLAN / PLAN ETAJ 3**

DATE/DATA	SCALE/SCARA	EXEMPLAR NR.	PROJ. PHASE/FAZA PROIECT	PROJ. No./Nr.PROIECT	DRWG. No/Nr. PLANSA
04/2006	1:50		Detailed design / Proiect tehnic	087/06	A-AR-005

It is prohibited to copy,multiply or print this document whitout written approval of the THE LOUIS BERGER GROUP, INC.
Este interzisa copierea, multiplicarea si imprumutarea documentelor fara aprobarea scrisa a THE LOUIS BERGER GROUP, INC.