



NOTA:

PERETII DIN GPS CARTON VOR FI DIN COCATAI VOR FI SEPARATI IN PANOURI DE 3 X 3M CU DIAFRAGME CONTRA PROPAGAREA FOCULUI

PLANOSILE SUSPENDATE VOR FI DIN COCATAI SAU SISTEMELE DE PRINDERE SI SUSPENDARE VOR FI DIN COCATAI RF 300MM

VOR FI SEPARATE PE DOUA DIRECTII DE MAX 20M CU DIAFRAGME CONTRA PROPAGAREA FOCULUI

PERNELE METALICE COR FI PROTEJATE LA FOC CU VORSEA TERMOPROUNTA REFUMIN

SIGNIFICANCE CATEGORY C - NORMALA

SIGNIFICANCE CLASS II, according to Normative P100

AMOUNT OF FIRE RESISTANCE II

BUILD-UP AREA ON GROUND = 782.8sqm

TOTAL BUILD-UP AREA=1070 sqm

CATEGORIA DE IMPORTANTA C - NORMALA

CLASA DE IMPORTANTA II, conform Normative P100

GRADUL DE REZISTENTA LA FOC II

SUPRAFATA CONSTRUCTA = 782.8sqm

SUPRAFATA DESFASURATA = 1070sqm

NOTA: ALL MEASUREMENTS SHOULD BE MADE ON SITE/TOATE MASURATORILE SA SE FACI LA FATA LOCIULUI

VERIFICATOR	NAME/NUME	SIGN/SEMANTURA	DEMANDE/DEBITA	REFERAT/EXPERTIZA NR. / DATA
M.F.P.T.				
PROJECT COORDINATOR/COORDINATOR PROIECT				
BUCHAREST SCHOOL INFRASTRUCTURE REHABILITATION / REABILITAREA INFRASTRUCTURII EDUCATIONALE IN MUNICIPIUL BUCURESTI				
DESIGNER/PROIECTANT				
BENEFICIARY/BENEFICIAR				
MUNICIPALITY OF BUCHAREST				
PRIMĂRIA MUNICIPIULUI BUCURESTI				
ELEMENTARY SCHOOL NO. 310/ȘCOALA GENERALĂ NR.310				
SPORT HALL/SALA DE SPORT				
ARCHITECTURAL WORKS/LUCRARE DE ARHITECTURA				
ATTIC FLOOR LEVEL				
PLAN TERASA				
PROJ. GRUPUL PROIECT				
THE LOUIS BERGER GROUP, INC.				
1:50				
08/2020				
B-AR-003				