DESIGNED BY	NAME/ NUME	SIGNATURA	
	Ing. Stefan Madan		
VERIFIED BY	**Ing. L. Cătoiu**		
VERIFIED BY	**Ing. Cristina Crep**		
SEF PROIECT			
DATE/ DATA	SCALE/ SCARA	EXEMPLAR NR.	PROJ. NR./NR PROIECT
05/2006	**1:50**	PROJ. PMS/SF/A/ZA PROIECT	**085/56**

Detaliu Detaliu
Proiect tehnic

DRWG. NR./NR. PROIECT

B- R/002

E.Bar interzice copierea, multiplicarea si reproducerea documentelor fara aprobarea sorisa a THE LOUIS BERGER GROUP, INC

It is prohibited to copy, multiply or print this document without approval of THE LOUIS BERGER GROUP, INC

BENEFICIAR/BENEFICIAR

MUNICIPALITY OF BUCHAREST
PRIMARIA MUNICIPIULUI BUCURESTI

SCHOOL NAME/ NUME SCOALA

Kinder-garten no. 250 / Gradinita nr. 250

TYPE OF WORKS/ LUCRARE

STRUCTURAL WORKS / LUCRARI DE STRUCTURA
CANTEEN BUILDING B / CANTINA CORP B

TITLE/ PLANSA

FIRST FLOOR SLAB
COFRAJ SI ARMARE PLACA PESTE DEMISOL

DESIGNED BY/PROIECTAT

VERIFIED BY/ VERIFICAT

PROJ. DIR/SEF PROIECT

Model	Data/Data			
M1				
M2				
M3				
M4				

PROJECT DESIGN COORDINATOR/ COORDINATOR PROIECT:

THE LOUIS BERGER GROUP, INC

SC CONSILIER CONSTRUCT SRL
str. Slupca nr. 6 - Bucuresti
J 40 / 7395 / 95 - R 7738294

BUCHAREST SCHOOLS INFRASTRUCTURE REHABILITATION / REABILITAREA INFRASTRUCTURII EDUCATIONALE IN MUNICIPIUL BUCURESTI

VERIFICATOR	NUME	SEMNATURA	CERINTA	REFERAT / EXPERTIZA NR. / DATA

OTEL / STEEL:
PC 52, OB 37

BETON / CONCRETE:
C4/5: EGALIZARI; EQUALISATION LAYERS
C8/10: BETON SIMPLU IN FUNDATII CONTINUE SUB ZIDURI,
FUNDATII IZOLATE SUB STALPI;
BUILDING CONCRETE IN CONTINUOS OR SINGLE FOUNDATIONS;
C12/15: BETON ARMAT IN CUZINETI, CENTURI, PLACA DE PARDOSEALA;
REINFORCEMENT CONCRETE FOUNDATIONS BLOCKS,
REINFORCEMENT CONCRETE BELTS,
REINFORCEMENT CONCRETE GROUND SLAB
C16/20: BETON ARMAT IN STALPI, PLANSEE, RAMPE DE SCARI;
REINFORCEMENT CONCRETE IN COLUMNS,FLOORS, STAIRWAIS,

PENTRU FIXAREA ARMATURILOR DE LA PARTEA SUPERIOARA
SE VOR FOLOSI CAPRE - 2 BUC. / mp

10 Ø 10 L= 1.10
OB 37 2 buc/mp

- Extras de armatura -
- Reinforcement Table -

Marca	Diam. [mm]	Lungimi [m]	Bucati	Lungime/Ø				
				OB 37	PC 52			
				Ø8	Ø10	Ø12	Ø16	
1	10	7.05	741		5224.05			
2	10	4.50	17		76.50			
3	10	4.40	26		114.40			
4	12	2.50	517			1292.50		
5	12	3.75	499			1871.25		
6	16	4.55	14				63.70	
7	16	3.85	14				53.90	
8	8	1815.00	mi	1815.00				
9	8	535.00	mi	535.00				
10	8	1.10	198	217.80				
Totalul lungimii/Ø [m]				2032.80	535.00	5414.95	3163.75	117.60
Masa/ml [kg/m]				0.395	0.395	0.617	0.888	1.578
Masa/Ø [kg]				802.11	211.10	3338.52	2808.82	185.61
TOTAL [kg]				7350 kg				